


2021 – 2023 Storm Drain Repairs Project

Basis of Design Report

Town Council Meeting - November 9, 2022

Town Maintained Storm Drain System

- 7 Residential Zones
- 20.8 Miles of Storm Drain Pipelines (109,824 Linear Feet in 1,092 Segments)
 - 88% Reinforced Concrete Pipe (RCP)
 - 7% Corrugated Metal Pipe (CMP)
 - 15% Polyvinyl Chloride (PVC) or High-Density Polyethylene (HDPE)
 - 10 Inch to over 12 Feet in Diameter
- ~ 8 Miles of Privately Maintained Storm Drain Pipelines



Major Storm Drain Program Efforts


Proactive Capital and Maintenance Plan

- **2022 – 2024 Pavement Rehabilitation Projects**

- Inspect Storm Drainpipe under roadway scheduled for rehabilitation
 - 2022 – Inspected 6,992 LF Storm Drainpipe
 - 2023 – Inspected 4,257 LF Storm Drainpipe
 - 2024 – Inspected 3,074 LF Storm Drainpipe

- **2021 – 2023 Storm Drain Repair Project – Town Wide**

- Prioritizes High Risk pipes for inspections first, such as Corrugated Metal Pipe (CMP) under roadways
- Completing 30,000 LF storm drainpipe video inspections
- 1,000 LF Corrugated Metal Pipe (CMP)
- 17,000 LF (Non-CMP Pipes > 36-inch)
- 12,000 LF (Non-CMP Pipes < 36-inch)
- Using NASSCO PACP inspection standard
- Prioritizes Cleaning and Maintenance work



Distance	Fault Observation	Time	Picture
176.0	Deposits Attached Encrustation Position: 4 To 8 Severity: None Cont Defect: F01 Percent: 15 Maint Weight: 3	00:08:54	OVER VOLTAGE! MH Z1-NODE-7/20/2022 MORAGA RD. MH N-0038 08:33 Deposits Attached Encrustation 176-FT
176.0	Deposits Settled Other Position: 4 To 8 Severity: None Percent: 25 Remarks: ROCK/BRANCHES/TRASH AT INVERT OF PIPE Maint Weight: 4	00:09:50	OVER VOLTAGE! MH Z1-NODE-7/20/2022 MORAGA RD. MH N-0038 08:34 Deposits Settled ROCK-BRANCHES/TRASH AT INVERT OF PIPE 176-FT
	Miscellaneous Water Level Severity: None Percent: 10	00:10:11	OVER VOLTAGE! MH Z1-NODE-7/20/2022 MORAGA RD. MH N-0038 08:35 Miscellaneous Water Level 176-FT



Project: MORAGA RD.	
Date: 7/20/2022 8:19:00 AM	Pipe Segment Reference: 0116
Street: MARAGA RD.	Upstream MH: Z1_NODE_0003
Length Surveyed: 176	Downstream MH: N-0038
Run Number:	Direction of Survey: Downstream
Height (Diameter): 60	Material: Reinforced Concrete Pipe

Distance	Fault Observation	Time	Picture
0.0	Access Point Manhole Severity: None Remarks: Z1_NODE_0003	00:00:25	MH Z1-NODE-7/20/2022 MORAGA RD. MH N-0038 08:25 Access Point Manhole Z1-NODE-0003 0-FT
0.0	Miscellaneous Water Level Severity: None Percent: 5	00:00:41	MH Z1-NODE-7/20/2022 MORAGA RD. MH N-0038 08:25 Miscellaneous Water Level 0-FT
46.3	Deposits Attached Encrustation Position: 4 To 8 Severity: None Cont Defect: S01 Percent: 15	00:03:09	MH Z1-NODE-7/20/2022 MORAGA RD. MH N-0038 08:26

CCTV Inspection Equipment

O&M Defect Grades

Grade	O&M Obstruction (%)
1	N/A
2	$\leq 10\%$ Obstruction of Flow
3	$< 10\%$ to $\leq 20\%$ Obstruction of Flow
4	$< 20\%$ to $\leq 30\%$ Obstruction of Flow
5	$> 30\%$ Obstruction of Flow



Pipe segment > Grade 3

- Structural and operational and maintenance (O&M) defects within a pipe are graded from 1 to 5, increasing in severity with 5 being the most significant.

- National Association of Sewer Service Companies (NASSCO) Pipeline Assessment and Certification Program (PACP) Condition Grading System

Structural Defect Grades

Grade	Description	Likelihood of Failure	Examples
1	Excellent Condition –Minor Defects	Unlikely in the foreseeable future	Surface Damage – Roughness Increased Crack – Circumferential
2	Good Condition – Minor to Moderate Defects	Unlikely to fail for at least 20 years	Surface Damage – Aggregate Visible Crack – Longitudinal
3	Fair Condition – Moderate Defects	May fail within 10-20 years	Joint Offset or Separation – Medium Crack – Multiple or at Hinges
4	Poor Condition – Significant Defects	Likely to fail within 5-10 years	Joint Offset or Separation – Large Hole or Broken – No Soil/Voids Visible
5	Immediate Attention Needed	Has failed or likely to fail within 5 years	Hole or Broken – Soil/Voids Visible Total Collapse



Grade 3 – Medium Joint Offset




Grade 4 – Severe Cracking




Grade 5 – Broken Hole with Visible Soil

STORM DRAIN INSPECTION RESULTS

- 180 Pipe Segments, 27% of the system, were CCTV Inspected
- Significant Maintenance Cleaning was Needed
 - 3,089 Linear Feet Cleaned
 - 2,303 Linear Feet Scheduled to be Cleaned
- 66% of Inspected Storm Drain Pipes (60 segments) have Grade 3 or higher Deficiencies and are in need of Repairs



BEFORE: ERODED BOTTOM



**DURING: FORMING NEW
STEEL GRID BOTTOM**



AFTER: GROUTED BOTTOM

HACIENDA STORM DRAIN REPAIR



MORAGA ROAD STORM PIPE CIPP LINING



Basis of Design Recommendations

- Repair Storm Drain Pipes with Grade 3 or Higher Deficiency
- Design Repairs for 22 Pipe Segments at an Estimated \$1,353,170 (construction)
 - 7 Point Repairs In Pipe
 - 4 Invert Paving Bottom of Pipe
 - 5 Install New Pipe Liner
 - 3 Remove and Replace Pipe Completely
 - 3 Heavy Cleaning and Reinspect Pipe
- 3,203 Linear Feet Additional Heavy Cleaning (ongoing)
- 38 Pipe Repair Segments are Deferred. The estimated construction cost (excluding design) is \$1,613,820 NPV

Staff recommends the Town Council receive and accept the Basis of Design Report for the 2021-2023 Annual Storm Drain Repairs Project (CIP 21-205); and provide staff with direction, if any, on the implementation of the Proposed Storm Drain Pipe Projects list.

